

Our Ref: No. OCAC-CAD-05/2014/-_____4447_____/Dated 04.10.2021

SHORT QUOTATION CALL NOTICE

Sealed quotations are invited from Registration firms for "Neon sign board for OCAC Tower and OCAC Tower main gate", Acharya Vihar, Bhubaneswar.

Sl. No.	Description of work	Size	Qty	Rate ₹.	Amount ₹.
1.	Supply, Delivery & Installation of Neon Sign Board As per below specification mater of Individual box type OCAC TOWER" (Blue colour Tube) English Letter Height 8 Feet. and OCAC Logo Height 10 Feet Total board Length 16 Feet x 152 Feet.(Approx) Neon Tube: 4 Line Glass Tube Letter Neon Tube made out of (12 mm dia and 1.2 to 1.4 mm wall Thickness) Egl, Egi, makes. (Imported) Electrodes: - Masonite, Egl & Egi makes. (Imported) Colour Tube: English Letter (Blue As per your Choice). & Logo Tube (As per your Logo Drawing) H.T. Transformers: - 15000/30ma 450 Watts, single- phase 220/230volts 50Hz. (Cannon or Egl & Egi (Durable) makes. Neon Gas: Egl & Egi for cool and bright lumination. (Imported) Neon Tube Coating: - Egl & Egi Laser. (Imported) L.T.Wires: 3/36 Flexible wires (Finolex) H.T.Cable:- PVC insulated copper Aug.cable 1.1KW 5 sq. mm. (Satwik & Finolex) makes. G.I.Sheet: - Box type latter made out of 24 & 26 gauge G.I.sheets. (Jindal, Bhusan & Rsp) Makes. (Drawing Attached)	No.	1		
2.	Sporting of Sign Board: -SIF Frame Structure for Supporting of Neon Sign Board made out of, Size of 150X50X5 mm, 40X40X5 mm, 35x35x5mm. 30x30x5mm M.S. Angles and Channels (16 Fet Height x 152 Feet Length (approx) Supporting OCAC TOWER English Letters and OCAC Logo	Kg.	1220		
3.	Concrete pillar including cost of sand, cement, chips & Labors etc. Mortar 600x600x600mm (L x B x H) for 624 Long pedestal of complete unit of signboard OCAC TOWER English Letters and OCAC Logo (Including labors & materials)	Job	1		
4	Supply, installation, testing and commissioning of L.T outdoor type distribution board made out of 1.6 mm thick CR sheet metal cubicle, duly acid treated for derusting, primered and painted with 2 coats of enamel paint of approved shade, dust, damp & vermin proof having hinged door and provision for cable/ conduit entry, earthing studs as per specification mentioned below duly factory wired conforming to the relevant ISS and as per special conditions of contract making good the damages caused complete as per the direction of EIC.				
a)	DB on roof.				
	Incomer: i) 1 no 40A TPN MCI.				
	Bus Bar : 4 nos 25 x 3mm Electrostatic Copper strip.				
	Outgoing : 6 nos. 25A DP MCB "C" curve.	Set	1		

5.	DB Control panel of Glow sign board.	Set	1		
	Supply, installation, testing and commissioning of street light control panel (Floor mounted) made out of 2mm thick CR sheet enclosure with 1 no. 40 Amp 4P MCI as incomer and 1 no 40A TPN MCB as outgoing 24 hrs. daily dial time switch and 70A A/C - 3 duty contactor for automatic on/off of the lights and suitable arrangement for termination of 4c x 16sqmm cable for entry /outgoing of 4c x 16sqmm cable, complete with locking arrangement as required as per technical specification and instruction of EIC.				
6.	Supply, delivery, laying & testing of following sizes XLPE insulated, PVC sheathed, strip/wire armoured aluminium conductor power cable of 1100 volt grade laid directly in ground/ on surface of wall/ column/ existing PVC pipework/ through G.I. pipe/ hume pipe as the case may be including excavation of earth in all kinds of soil & rock, sand cushioning, protective covering, refilling the trench with sand, brick covering and cable end termination but excluding the cost of G. I. pipe/ hume pipe compete with making good the damages caused as required and as per direction of Engineer-in-charge.				
a)	4 core x 16 sqmm PVC Al. Ar. cable.	Mtr.	50		
7.	Termination of following size Al. Ar. Cable with brass cable gland and Al. socket 4 core x 16 sqmm PVC Al. Ar. cable.				
a)	4 core x 16 sqmm PVC Al. Ar. cable.	Nos.	2		
8.	Supply and laying of 8 SWG wire.	Mtr.	150		
9.	Transporting to (G+7 Floor Terrace) Installation testing & Commissioning charges on Neon sign board.	Set	1		
OCAC TOWER MAIN GATE SS GLOW SIGN BOARD					
10.	SS Steel Sheet	Kg.	150		
11.	MS Channel Angle	Kg.	50		
12.	Light (NION)	Sq.ft	54		
13.	Fabrication and handling	Kg.	200		
14.	Cable and accessories	LS	1		
	GST @18% including				

General Terms and conditions :

1. Location of the Project :

The sign board works as per specifications will be done in the OCAC Tower and OCAC Tower main gate at Plot No.N-1/7-D, Acharya Vihar Square, P.O. RRL, Bhubaneswar-751 013.

2. Time of completion of Project :

All erection, installation and supply work shall be completed within 15 days from the date of issue of work order.

3. Eligibility of the bidder .:

- (i) The bidder shall submit proof of executing similar types of work.
- (ii) The bidder shall submit an EMD of Rs.1,00,000.00 in shape of DD payable to Odisha Computer Application Centre, Bhubaneswar.

- (iii) Non-refundable tender paper cost of Rs.5000.00.
- (iv) The bidder shall submit copies of PAN No. and up to date GST clearance failing which the bids will not be accepted.

4. Payment :

- (i) Payment will be made after successful execution of the work, measurement done and completion certificates issued by the proper authority of Odisha Computer Application Centre for each item of work.

5. Warranty :

The Neon sign boards shall have a warranty of 1 year against any manufacturing and printing defects.

6. Delay in completion of the Project :

The time schedule for completion of the project as mentioned in Clause 2 above is very important and the bidder must take utmost care to complete the work in schedule. If the work is delayed for any reason for which Odisha Computer Application Centre or the authorities in charge of the concerned site are not responsible, a penalty @5% of the cost of the work order will be charged to the bidder for a delay of one week or part thereof.

The sealed tender should reach the undersigned on or before 3:30 P.M. of dated 21.10.2021. The authority reserves the right accept / reject any or all the tender without assigning any reason thereof.

R. G. S.
21/10/2021

General Manager(Admn)

- 1. PA to CEO, OCAC for kind information of CEO, OCAC.
- 2. G.M. (Admin), OCAC for kind information
- 3. Deputy General Manager(Finance), OCAC for kind information.
- 4. Notice Board for information of all bidders.