

**SHORT TENDER CALL NOTICE**

Sealed quotations are invited from Government approved Civil Contractors for the "Repair & restoration of sewerage line with cleaning of old line & laying of new connection including dismantling of old damaged chamber & construction of new man hole chamber etc. complete of front side at OCAC Building", Acharya Vihar, Bhubaneswar as per specification below :

Sl. No.	Description of work	Qty	Unit	Rate ₹.	Amount ₹.
1.	Dismantling and removing old tiled walling/flooring including removing the base course and stacking the useful materials for reuse and removing the debris within 50m lead	44.45	Sqm.		
2.	Earth for excavation of foundation in hard/gravelly soil including rough dressing and levelling the bed and depositing the excavated earth away from the work site by mechanical carriage with all leads, lifts and delifts etc. complete as per the direction of Engineer-in-Charge.	37.89	Cum.		
3.	Sand filling in foundation & plinth with water & ramming with labour complete as per the direction of Engineer-in-Charge.	7.22	Cum.		
4.	Cement Concrete (1:1.5:3) with 12mm size h.g.c.b. chips for RCC work including hoisting and laying including cost, conveyance and royalty of materials and labour charges etc. complete as per the direction of the Engineer-in-Charge	4.66	Cum.		
5.	Supplying all materials, labour and T&P for fixing SWR PVC Pipe and fitting walls with nails, bobbins and wooden plugs as per specification or laying in trenches excluding earth work in excavation and refilling the trenches as per the direction of Engineer-in-Charge.	4	Nos.		
6.	12mm thick cement plaster (1:6) for brick work with all cost, conveyance, royalty etc. complete as per the direction of Engineer-in-Charge.	27.87	Sqm.		
7.	Supplying all materials, labour and T&P for cutting groves in pucca floor and walls for taking G.I. Pipes and fitting / PVC pipe and fitting and making good to the damages all complete as per the direction of Engineer-in-Charge.	12	Mtrs.		
8.	Supplying all materials, labour and T&P for cutting holes through existing brick work including making good to the same in cement mortar (1:4) for taking G.I. pipes and fittings / PVC pipes and fitting all complete as per the	6	Nos.		

	direction of Engineer-in-Charge.				
9.	Supplying, all materials, labour T & P for constructing man hole chamber / Gali chamber with R.C.C. Slab in (1:1:5:3) mix foundation concrete (1:4:8) inside plaster 12mm brick with - c.m. (1:3) brick work with KB Bricks, with crashing strength cost not less than 75 kg / sqm in c.m. (1:5) finished smooth complete back side of extension block of PPF as per the direction of the Engineer-in-Charge.	5	Nos.		
10.	Shifting of Garbage from old Sewerage line to outside by sewerage vehicle including transportation and Cleaning of main drain with lifting moad and weast materials and shifting to outside with the help of labour etc complete as per the direction of Engineer-in-Charge.	1	Job		
	<b>Total</b>				
	<b>GST @ 12%</b>				
	<b>Grand Total</b>				

**Terms and conditions of execution :**

1. The dealer / registered contractor shall submit copies of valid authorisation PAN / GST clearance certificate.
2. Tender should be submitted within 5 days of Notice.
3. The work shall be completed within 15 days from the date of issue of work order.
4. 100% payment shall be made after completion of work and verification thereof as per Purchase Order/ Work Order.

The sealed tender should reach the undersigned on or before 3:30 P.M. on dated 20.04.2022. The authority reserves the right accept / reject any or all the quotations without assigning any reason thereof.



**General Manager(Admin)**

1. PA to CEO, OCAC for kind information of CEO, OCAC.
2. G.M. (Admin), OCAC for kind information
3. Deputy General Manager(Finance), OCAC for kind information.
4. Notice Board for information of all bidders.
5. Sri B. K. Mohanty, DPO to publish the notice in OCAC website.