

SHORT TENDER CALL NOTICE

Sealed quotations are invited from Government approved Civil Contractors for the "Painting of conference hall, Joint Secretary office chamber & tile flooring of driver room front with other miscellaneous civil works of OCAC Building ", Acharya Vihar, Bhubaneswar as per specification below :

Sl. No.	Description of work	Qty	Unit	Rate ₹.	Amount ₹.
1.	Earth for excavation of foundation in hard / gravelly soli including rough dressing and leveling the bed and depositing the excavated earth away from the work site by mechanical carriage with all leads lifts and delits etc. complete as per the direction of engineer- in-charge.	7.48	Cum		
2.	Sand filling in foundation and plinth with water & ramming with roller complete as per the direction of engineer- in- charge.	3.74	Cum		
3.	Cement concrete (1:3:6) with 40 mm and downgraded size broken hard granite metal including cost, conveyance and royalty of material , labour charge etc. complete as per the direction of engineer-in-charge.	3.07	Cum		
4.	Cement concrete (1:2:4) with 12 mm and downgraded size broken hard granite metal including cost, conveyance and royalty of material, labour charge etc. complete as per the direction of engineer-in-charge.	3.07	Cum		
5.	Fixing tiles in floor/ wall, treads or steps and landing on granait joined with neat cement slury mixed with pigment to match the shades of the granait including rubbing and polishing etc. complete as per the direction of the engineer-in-charge.	26.52	Sqm.		
6.	Scraping old paint with scrapers, sand papering and if required washing with soap water or soda including scraffolding charges above 5m high and upto 8m height etc. complete as per the direction of engineer-in-charge.	37.66	Sqm.		
7.	Priming one coat with any approved primer on wall surface with all cost as per the direction of Engineer-in-Charge.	37.66	Sqm		
8.	Wall painting two coat with plastic emulsion paint /weather coat of approved shade to give an even shade including all cost of materials, labour etc. complete as per the direction of Engineer-in-charge.	37.66	Sqm		


9	Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and seven surface to receive painting including cost of scaffolding staging charges with cost of all materials, taxes, labour T & P etc. complete as per the direction of Engineer-in-charge	37.66	Sqm		
10	Supplying fitting and fixing of 48' ceiling fan aluminum body, copper winding, high speed ceiling fan etc but excluding GST compete as per the direction of engineer -in- charge (make Crompton model -jura polycab model vital polar model wipro etc.)	2	Nos.		
11	Recessed wiring to submain in 2x4 sqmm FR PVC insulated single core multistand copper conductor of ISI marked conforming top IS 694/1990 in 20mm dia non-metallic heavy duty flexible conduit 1.6mm thick along with 1x1.5 sqmm FR PVC insulated single core multistand copper conductor as earthwire as equired (make of wire finolex/L&T / anchor/ HAVELS / v guard)	35	Mtrs.		
12	Supply, installation testing and commissioning of 32 amp DP switches of the following capacity (IS 13940 part 3/1993) on existing surface/ wall mounting make -/L&T/ HAVELS C&S/	3	Nos.		
13	Man/woman labour for use of shifting garbage, dismantling damaged items etc. (10 labours 1 day)	10	Nos.		
14	Supplying all materials, labours, T&P and fitting and fixing of the following size of 25mm UPVC pipes part No. 70000220 make Ashirvad with socket and screw joints in walls and floors including supplying of required number of fittings of approved make including cutting threads to pipes and pipes to length, including wastage, etc for fitting to the walls with supply of holder ats, clamps, fixing wooden plugs in walls, including testing of pope line for water tightness complete as per IS specification including cost, conveyance and taxes of all materials all complete as per PH specification and direction of Engineer-in- charge.	18.29	Mtrs.		
	Total				
	GST @ 12%				
	Grand Total				

Terms and conditions of execution :

1. The dealer / Government registered contractor shall submit copies of valid authorisation PAN / GST clearance certificate.
2. Tender should be submitted within 7 days of Notice.
3. The work shall be completed within 15 days from the date of issue of work order.

4. 100% payment shall be made after completion of work and verification thereof as per Purchase Order/ Work Order.

The sealed tender should reach the undersigned on or before 3:30 P.M. on dated ~~03.03~~^{18.04}.2022. The authority reserves the right accept / reject any or all the quotations without assigning any reason thereof.


14/03/2022
General Manager(Admin)

1. PA to CEO, OCAC for kind information of CEO, OCAC.
2. G.M. (Admin), OCAC for kind information
3. Deputy General Manager(Finance), OCAC for kind information.
4. Notice Board for information of all bidders.
5. OCAC Web Site .